

SHIMOGA DIVISION.

Abstract Notification dated 9th December 1937.

The attention of the public is hereby invited to the advertisement published on pages 2090-2091, Part VI of the *Mysore Gazette* dated 16th December 1937, calling for tenders for constructing an anicut at Harakere Voddu near Harakere Village, Shimoga Taluk.

Last date of receiving tender is 8th January 1938.

P. SUBBA RAO,

Executive Engineer.

KADUR DIVISION.

Notification dated 21st December 1937.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kadur Division, up to 2 P.M. on 24th January 1938, for the work of constructing a block of 5 units for Line Men's Quarters at Lingadahalli, Tarikere Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1938.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chikmagalur between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 190 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for the work of constructing a block of 5 units for Line Men's Quarters at Lingadahalli, Tarikere Taluk," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of disputes about rates, quantities, measurements, quality of work, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract estimate for constructing a block of 5 units for Line Men's quarters at Lingadahalli, Tarikere Taluk.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		
1	Earthwork excavation for foundation and filling in basement	C.yds.		40	
2	Burnt-stone jelly concrete in lime mortar	C.ft.		354	
3	Size-stone in clay with bond stone at every 6' apart	C.ft.		1,077	
4	Burnt-brick in clay	"		2,677	
5	Burnt-stone slabs, 4" to 6" thick, dressed and fixed	S.ft.		342	

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		
6	Chunam mortar plastering	S.qr.		56.50	
7	Pointing with cement mortar	"		2.01	
8	White-washing, 2 coats	"		56.50	
9	Colour-washing to basement	"		2.01	
10	Teakwood wrought and put up including wood oiling	C.ft.		66.10	
11	Roofing with 1st class Mangalore tiles on teak reepers 2"×1"	S.qr.		18.10	
12	Ridge tiles set in mortar and cement pointed	R.ft.		89	
13	Providing and fixing Mangalore Ventilating tiles	No.		20	
14	Doors with teakwood frames and battened shutters, 1" thick with iron fittings, hinges, etc., complete	S.ft.		195	
15	Windows with teakwood frames and battened shutters, 1" thick with iron bars $\frac{5}{8}$ " thick hinges, etc., complete	"		75	
16	Shelves with teakwood frame with shutters planks 1" thick	"		60	
17	R. C. perforated ventilators	"		23	
18	Providing and fixing expanded metal with teakwood frames 2"×3"	"		300	
19	Flooring with 3" chunam concrete over $\frac{1}{2}$ " cement concrete, cement plastering $\frac{1}{2}$ " coloured and lined, etc., complete	S.qr.		9.24	
20	Providing and fixing teakwood eave board 9" wide and 1" thick	R.ft.		176	
21	Providing mortar band 6"×6" in burnt brick in mortar with plastering and white-washing	"		29	
22	Silver gray painting, 2 coats	S.qr.		14.90	
23	Constructing sinks	No.		5	
24	Providing and fixing stone mortar and pestle	"		5	
25	Constructing a dwarf wall in front verandah with burnt brick in mortar	R.ft.		55	
26	Removing debris and levelling ground	L. S.			

Notification, dated 1st January 1938.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kadur Division, up to 2 p.m. on 24th January 1938, for the work of constructing a High Level Causeway across the Halla near Mudgere Pumping Station on Mudgere-Belur Road. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1938.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chikmagalur, between the hours of 11 a.m. and 5 p.m.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 300 (three hundred only) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for the work of constructing a High Level Causeway across the Halla near Mudgere Pumping Station on Mudgere-Belur Road," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.
9. Rates once tendered will not be enhanced on any account.
10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.
11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.
12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.
13. The quantities as estimated are only approximate and are liable to alterations, omissions, deductions or additions at the discretion of the Executive Engineer. The tender rates will hold good for any quantity, whether higher or lower than those estimated for.

Abstract estimate for constructing a High Level Causeway across the Halla near Mudgere Pumping Station on Mudgere-Belur Road.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		
1	Earthwork excavating foundation in hard gravel soil mixed with shingle;	C.yd.	..	198	
2	Burnt stone jelly concrete in surki combination mortar 1 : 6 proportion	C.ft.	..	1,014	
3	Burnt size-stone in surki mortar with bond stones complete	C.ft.	..	2,143	
4	Cutwaters in cut stone in surki mortar	„	..	68	
5	Cement pointing to masonry 1 : 3 proportion	S.qr.	..	8.78	
6	Reinforced cement concrete slabs complete, cast in situ with tension and compression, reinforcements, cement plastered and finished smooth including centring charges, etc., complete	C.ft.	..	1,290	
7	New rough stone pitching with jelly packing	C.yd.	..	52	
8	Collecting, breaking and stacking blasted granite metal, including average lead of 2½ miles	C.yd.	..	100	
9	Collecting, stacking gravel with bed	„	..	50	
10	Picking metal surface of road	S.yd.	..	1,320	
11	Spreading and consolidating metal by stone roller	C.yd.	..	100	
12	Spreading and consolidating gravel by stone roller	„	..	50	
13	Collecting and spreading sand with bed	„	..	20	
14	Iron chains with circular R. C. pillars of 1 foot dia. 2' height at 14 ft. intervals on either side of Causeway	R.ft.	..	172	
15	Providing expansion joints at joints of slabs 14 ft. C to C	„	..	60	
16	Bonding iron hooks	No.	..	28	
17	Water diversion charges	L. S.	..	..	
18	Bailing out water during excavating foundation	„	..	..	

C. R. IYENGAR,
Executive Engineer.

OFFICE OF THE EXECUTIVE ENGINEER, MARCONAHALLI RESERVOIR
DIVISION.

Notification.

Quotations are invited for the purchase of serviceable empty steel casks of 42 Imperial gallons capacity available for sale at the office of the Executive Engineer, Marconahalli Reservoir Division, so as to reach the undersigned on or before the 25th January 1938. The rates quoted should be—

- (1) Ex-stores—Marconahalli.
- (2) Ex-Divisional stores—Water Supply Division, Bangalore.